

	TENDER DOCUMENT TYPE	ANNEX	TENDER DOCUMENT REFERENCE	QUESTION	ANSWER
1	GENERAL	n/a		Is there duty relief for this project – importation of equipment and materials?	Yes.
2	GENERAL	n/a		Are we able to use the Heritage Wharf building for offices, kitchen and bathrooms? This will reduce costs and also allow for safer working room on site as space will be limited. If possible, what are the associated monthly costs for using this space?	No. Please refer to addendum 2, question 18.
3	GENERAL	n/a		Confirm pre-cast elements, steel rebar (in-situ) and fly ash all to be on same ship – delivered to Cross Island?	Please refer to addendum 2, question 8, paragraph 3) and 5).
4	GENERAL	n/a		Confirm that there will be no requirement for the use of silt curtains or any other marine protection devices/procedures at any stage of the project.	No.
5	GENERAL	n/a		What is the maximum unassisted weight (PSF) that can be placed on the existing concrete deck?	A recent study from November 29, 2017, states the following: 1. Maximum permissible uniformly distributed live load over the concrete deck area (i.e. the occupancy live load or passenger assembly live load): 100 psf; and 2. Maximum permissible axle load from a small truck or bus: 3500 kg single rear axle load. All tandem axles shall be prohibited. The contractor to verify the slab capacity before demolition. Study will be available for the selected contractor.
6	GENERAL	n/a		At the site meeting it was verbally agreed that the demolition material (existing concrete deck and associated concrete elements) will be allowed to fall into water and be retrieved prior to start of pile works. Please confirm this is still an approved option?	Yes. The client will thoroughly check the seabed prior to construction.
7	GENERAL	n/a		Will the pile survey be distributed to all tenderers (as previously mentioned)?	No. Please refer to addendum 2, question 13.
8	GENERAL	n/a		Are there any further details as to connection of new concrete dock to existing shoreline or are we still to carry the indicated \$25,000.00 provisional sum?	Carry the indicated \$25,000.00 provisional sum.
9	GENERAL	n/a		Once we install permanent slabs - what is maximum weight (PSF) allowed on deck?	Standard HS20 loading with 270 PSF.